




PROPOSED PLANTING SCHEDULE

| KEY | QTY | SYMBOL | BOTANICAL NAME | COMMON NAME | SIZE | REMARKS |
|---------------------------|-----|--------|----------------------------|------------------------|-----------|---------|
| SHADE TREE(S) | | | | | | |
| AR | 8 | | ACER RUBRUM | RED MAPLE | 3-4" CAL. | B+B |
| TOTAL | 8 | | | | | |
| EVERGREEN SHRUB(S) | | | | | | |
| PL | 16 | | PRUNUS LAUROCERASUS | SKIP LAUREL | 42"-48" | B+B |
| SP | 15 | | STANDISHII X PLICATA | GREEN GIANT ARBIVITE | 9-10' | B+B |
| TOTAL | 31 | | | | | |
| SHRUBS | | | | | | |
| SLP | 28 | | SPIREA X 'LITTLE PRINCESS' | LITTLE PRINCESS SPIREA | 24" HT | 1 GAL. |
| TOTAL | 28 | | | | | |

NOTE:
1. IF ANY DISCREPANCIES OCCUR BETWEEN AMOUNTS SHOWN IN THE PLAN AND THE PLANT LIST, THE PLAN SHALL DICTATE.

PLANTING AND LANDSCAPING NOTES:

- ALL PLANTS SHALL BE HEALTHY OR NORMAL GROWTH, WELL ROOTED, FREE FROM DISEASE AND INSECTS. QUALITY AND SIZE OF PLANT MATERIAL SHALL CONFORM TO THE AMERICAN SOCIETY OF NURSERYMEN STANDARDS, LATEST EDITION GRADING CODE OF NURSERY STOCK AND BE OF NUMBER ONE GRADE.
- POSITION TREES AND SHRUBS AT THEIR INTENDED LOCATIONS AS PER THE PLANS AND SECURE THE APPROVAL OF THE ENGINEER BEFORE EXCAVATING PITS, MAKING NECESSARY ADJUSTMENTS AS DIRECTED. ANY SUBSTITUTIONS ARE TO BE APPROVED BY THE ENGINEER.
- PLANTING PITS SHALL BE DUG WITH LEVEL BOTTOMS, WITH WIDTH TWICE THE DIAMETER OF ROOT BALL AND 6" DEEPER THAN THE LENGTH OF ROOT BALL. EACH PLANT PIT SHALL BE BACKFILLED WITH THE FOLLOWING PREPARED SOIL MIXED THOROUGHLY:
 - ORGANIC TOPSOIL FROM NATURES CHOICE CORP -1 800 637 4140
 - 3 CUBIC FEET/PLANTING PIT FOR SHADE OR EVERGREEN TREES
 - 1 CUBIC FOOT FOR SHRUBS
- IMMEDIATELY AFTER PLANTING, STAKE ALL TREES IF NECESSARY TO PREVENT DAMAGE FROM WIND (LODGE-POLE STAKES LENGTH AS REQUIRED) . FASTEN TREES TO UPPER END OF STAKE IN AT LEAST TWO (2) PLACES USING HOSE TYPE TIES.
- WATER IMMEDIATELY AFTER PLANTING. WATER SHALL BE APPLIED TO EACH TREE AND SHRUB IN SUCH MANNER AS NOT TO DISTURB BACKFILL AND TO THE EXTENT THAT ALL MATERIALS IN THE PLANTING HOLE ARE THOROUGHLY SATURATED.
- ALL PLANTING AREAS SHALL BE GRADED AND MAINTAINED TO ALLOW FREE FLOW OF SURFACE WATER.
- ALL PLANTING SHALL BE MAINTAINED OR REPLACED IF NECESSARY BY THE CONTRACTOR FOR AT LEAST TWO GROWING SEASONS
- ALL PROPOSED PLANTINGS ALONG THE ACCESS DRIVEWAYS SHALL BE KEPT TO A MATURE HEIGHT OF NO GREATER THAN THIRTY (30) INCHES AND THE SHADE TREES BRANCHES TRIMMED UP TO A HEIGHT OF 7, MEASURED FROM THE DRIVEWAY PAVEMENT .



| | |
|---|--|
| AWZ ENGINEERING, INC. ENGINEERS • SCIENTISTS • CONSULTANTS Main Office: 150 River Road, Suite B3, Montville, NJ 07045 Pennsylvania Office: Scranton, PA 18504 Tel: 973-588-7080 Fax: 973-588-7079 www.awzengineering.com e-mail: info@awzengineering.com New Jersey Certificate of Authorization No.: 24GA28118400 Pennsylvania Certificate of Authority No.: 3771354 | DRAWN BY: [Blank] EC: [Blank] DATE: 04/20/25 DESIGNED BY: [Blank] AK: [Blank] DATE: 04/20/25 APPROVED BY: [Blank] AK: [Blank] DATE: 04/20/25 |
| | ADNAN A. KHAN, P.E., C.M.E. PROFESSIONAL ENGINEER P.A. LICENSE NO. 4862E N.Y. LICENSE NO. 08645 M.D. LICENSE NO. 41843 |
| TAX LOTS 1 & 5 219-227 BROAD STREET TOWNSHIP OF BLOOMFIELD ESSEX COUNTY, NEW JERSEY | BLOCK 516 LANDSCAPING EXHIBIT |
| JOB NUMBER: 24-0401 | EX-01 SHEET 1 OF 1 |